

CATEGORY	WELL	STATUS	LATEST ONLINE DATE	CURRENT PRODUCTION	PRODUCTION OPPORTUNITY	INCREMENTAL PRODUCTION			INCREMENTAL GL RATE	CURRENT BOTTLENECK
						MMSCFD	BOPD	BWPD		
EXISTING WELLS	UPA-01X	SHUT IN	Jul-17	-	20 BOPD / 2400 BWPD	0	5	500	1.1	Production choke kept at 80/64". Limitation on CPP produce water handling & GLC
	UPA-02X	SHUT IN	Apr-17	-	20 BOPD / 2450 BWPD	0	15	1050	1	Production choke kept at 40/64". Limitation on CPP produce water handling & GLC & 2" GL F/L Unavailable
	UPA-03X	FLOWING	-	24.6 BOPD / 1204 BWPD	35 BOPD / 2165 BWPD	0	10	656	1.22	Production choke kept at 80/64". Limitation on CPP produce water handling.
	UPA-04X	FLOWING	-	44 BOPD / 1774 BWPD	51 BOPD / 2070 BWPD	0	7	130	0.3	Limitation on CPP produce water handling & GLC
	UPA-05X	SHUT IN	Aug-18	-	96 BOPD / 4800 BWPD	0	96	4800	1.83	Limitation on CPP produce water handling & GLC & GLM Orifice Completion Clogged by Scale & Tubing S
	UPA-06X	FLOWING	-	325 BOPD / 3427 BWPD	440 BOPD and 5000 BWPD	0	115	1573	0.4	N/A
	UPA-11	FLOWING	-	0.1 MMSCFD / 184 BOPD / 2328.3 BWPD	0.3 MMSCFD / 204 BOPD / 2450 BWPD	0	20	175	0.5	Limitation on GLC
						0	268	8704	6.35	

Tabel 3. Loss Production Opportunity

- Atas dasar ini, maka SIPL mengajukan usulan penambahan unit Gas Lift Compressor. Untuk penyediaan unit permanen akan membutuhkan waktu yang lama sehingga LPO akan semakin meningkat karena beberapa sumur produksi akan dimatikan demi mengakomodir sumur-sumur development yang baru dibor untuk diproduksi.
- Oleh karena itu SIPL mengusulkan untuk Rental Gas Lift Compressor sementara unit permanent akan secara paralel diajukan melalui mekanisme AFE usulan baru.
- Unit permanen direncanakan akan mengkonversi MP2 Compressor eksisting menjadi Gas Lift Compressor Feeder, sehingga lingkup pekerjaan tidak menambah unit baru di fasilitas produksi melainkan hanya modifikasi.

No.	Deskripsi	2018						2019						2020	
		Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
1	Engineering (in-house) assessment & design untuk MPC-2														
2	Engineering (consultant) detail design, isometric dan BOM														
3	SKK Migas Approval														
4	Pengadaan unit MP Compressor (replacement) dan assesoriesnya														
6	Fabrikasi MP Compressor-2 dan delivery time														
5	Pengadaan Material piping, Valve-valve dan assesoriesnya														
7	Fabrikasi dan Pemasangan piping														
8	Pemasangan Compressor dan hook up spool														
9	Commissioning dan start up														

Tabel 4. Rencana Jadwal Konversi MP2 Compressor menjadi Gas Lift Compressor Feeder.

- Pengadaan unit Compressor untuk menjadi feeder Gas Lift Compressor akan dimulai di bulan Oktober 2018, sesuai dengan mekanisme pemesanan unit dengan vendor, diperlukan fabrikasi selama 14 bulan dan kemudian pengiriman (delivery time) selama 2 bulan. Oleh karena itu, periode rental akan dilakukan selama 16 bulan dimulai dari bulan November 2018 dan diharapkan berakhir di february 2020.

MP2 as GL Booster	Approach 1	Approach 2	Approach 3
Compressor Model	C505U	C408A	C406A
Rotor Configuration	5 x std-low flow impellers	7 x hi-std flow impellers	6 x std flow impellers
DESCRIPTION			
Compressor Restage by means of	Compressor Replacement	Compressor Replacement	Bundle Replacement
Workscope	Extensive	Moderate	Minimal
Estimated Sell Price, US\$ each	\$2,200,000 - \$2,400,000	\$2,250,000 - \$2,300,000	\$1,600,000 +
Estimated Lead time, basis EXW Solar USA	11- 12 months	12 - 14 months	10 + months

Tabel 5. Penawaran dari vendor mengenai periode fabrikasi kompressor.

- Lingkup pekerjaan rental Gas Lift Compressor diantaranya, Biaya rental Unit Compressor, Biaya fabrikasi dan material perpipaan yang akan di modifikasi serta Biaya Instalasi.
- Sesuai dengan production profile SIPL dan forecast kebutuhan Gas Lift kedepan, Maka diperlukan unit Gas Lift Compressor yang bisa menghantarkan sebanyak Maksimum 14 MM. Sehingga total kebutuhan Gas Lift Maksimum 39 MM sampai akhir periode rental di February 2020, bisa terpenuhi (14 mmscfd dari Rental, dan 25 mmscfd dari eksisting).